

Installation Instructions

The following instructions are general guidelines. Installation should be performed by a qualified electrician in accordance with the National Electrical Code and any applicable local codes. Read through the entire instructions before beginning installation. Contact Celestial Lighting for further assistance.



Unroll Corona lightstrip and cut to length. Ensure that no single run exceeds maximum run length (20ft for lightstrips with 2.4" socket spacing; 25ft for lightstrips with 3" socket spacing).


Multiple sections of lightstrip may be daisy-chained together, so long as total length of lightstrip sections does not exceed the maximum run length.

Do not include feed wire or connecting wire when calcuating run lengths.

Example: 20ft on one continous section


Feed wire

Example: Two sections of 10ft to create 20ft run




Step 2 (A)

Screw mount lightstrip to surface. Use standard #4 screws through mounting holes on each socket.



Step 2 (B) If using Mounting Channel: cut channel to length; screw mount channel to surface; snap in lightstrip.



Step 2 (C) If using Linear Lens and Linear Channel; cut channel and lens to length; screw mount channel to surface; snap in lightstrip. Snap in lens after all other installation is complete.

